BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT31401

APPROVED SCHEDULE - B

No. E/BTP/BBMP/E-PMT/02/2018-19, Date: 26.07.2018

Providing Basic facilities for Ganesha Immersion at Hebbal Lake Kalyani in Kodigehalli ward no. 8.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of ABBANNA ABBANNA (SHILPA ENTERPRISES.)	
				In Figures	In Words
1	150	Supply of Drinking Water through water tankers of Capacity 6000 Liters and Hiring of Water Tanker Hiring of Tractor 40HP including cost of warer and Engaging Heavy Mazdoor to deliver water including cost of fuel lubricants men and machinary etc. complete including	no	500.0	Rupees Five Hundred Only
2	12	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal Component	cum	750.0	Rupees Seven Hundred Fifty Only
3	90	Hire charge of pumping water 3.5 KL/hr capacity Pump	Hr	45.0	Rupees Forty Five Only
4	300	Providing Causal Labours (Unskilled mazdoor Heavy)	No	240.0	Rupees Two Hundred Forty Only
5	1590	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis as per the engineer in charge.	M	60.0	Rupees Sixty Only
6	54000	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 60ft x 40ft = 2400 sqft)	Sft	7.0	Rupees Seven Only
7	450	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft)	Rft	15.0	Rupees Fifteen Only
8	720	Hire Charge for Armless Plastic Chairs	No	4.0	Rupees Four Only
9	300	Hire Charge for Wooden Table of Size 6ft x 2ft	No	40.0	Rupees Forty Only
10	2250	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD SR 2010-11 P.55/I.6 III b)	M	7.0	Rupees Seven Only
11	105	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges (PWD SR 2016-17 (P.XXXXVII / I.92)	Hr	600.0	Rupees Six Hundred Only
12	420	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time	No	240.0	Rupees Two Hundred Forty Only
13	10	1031 - Providing J.C.B Excavator on Hire basis including Operator and Fuel (P. XXXXVI/I. 23) PWD SR 2016-17	Day	6600.0	Rupees Six Thousand Six Hundred Only

Signature of the Contractor

16/10

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

16/10